

**ADDENDUM NO. 2**

**DATE:** April 28, 2015  
**PROJECT:** Marquette Area Public Schools – 2016 Improvements  
**OWNER:** Marquette Area Public Schools  
**BID DATE:** ~~Tuesday, May 3, 2016 at 10:00 am~~ **Thursday, May 5, 2016 at 10:00 a.m.**

The following shall be incorporated into the Contract Documents dated **7 APR 2016**.

**DRAWINGS**

---

General Notes:

Asbestos contractor will be providing air monitoring during construction.

D101 – Basement Mechanical Demolition Plan

Existing steam and condensate main piping in tunnel and crawlspaces adjacent and under Kaufmann Auditorium and the gym shall be abandoned in place. Where required space is need to run new piping up through floor remove piping as required. All piping to terminal units shall be demolished. New piping shall use existing penetrations where practical. All piping passing through existing penetrations shall utilize escutcheons to cover space not covered by new piping.

Note: Owner will remove asbestos in areas mentioned above including selective areas of duct insulation where work will occur to install new piping.

Contractor responsible for replacing insulation on duct where removed to allow piping installation.

Sheet M101 Basement Mechanical Plan

Piping shall only cross corridor and piping running along walls is not allowed.

Sheet M103 Second Floor Mechanical Plan

Radiation above the toilet rooms at the Balcony will be abandoned in place. No new piping is required to the 2 units.

Sheet M301 Details and Schematics

Chilled water control valves shall be replaced in units LCAC-1 and LCAC-2. Chilled water piping modifications and insulation repair shall be included. Use of transducers shall not be allowed

Sheet M301 Details and Schematics

Pricing shall be assumed that Gym AHU does not have face and bypass dampers.

**End of Addendum No. 2**