

ADDENDUM NO. 2

DATE: January 18, 2019
PROJECT: Miller Road Streetscape
OWNER: City of Swartz Creek
BID DATE: Wednesday, January 23, 2019 at 10:00 am

This addendum shall be considered part of the Contract Documents.

GENERAL

Engineer's response to inquiries.

RFI. 1 – For the decorative walls, the plans indicate a precast concrete cap while the specs indicate limestone.

For decorative walls, walls columns, and fence columns, the cap shall be limestone.

RFI. 2 – The specification for how the decorative walls will be paid describes the following: “Vertical measurement shall include only the exposed wall above finished surface.” How can the contractor determine this?

Payment for the Decorative Wall will be in square feet for roadside face features only, measured from finished surface to top of limestone cap. This includes the decorative walls, the wall columns, and the columns that are used in conjunction with the Decorative Iron Fence.

RFI. 3 – Will grading for the streetscape items (not parking lot) be paid under earth excavation?

Grading of streetscape items including but not limited to:

- Sidewalk, Conc, 4 inch, Modified
- Aggregate Base, 4 inch, Modified
- Excavation, Earth
- Embankment, CIP
- Hand Patching
- HMA, Repair

Shall be considered incidental to each pay item and will not be paid separately.

End of Addendum No. 2